

# NUCLEAR POWER PLANT KRŠKO

## Chemistry Department

### TECHNICAL SPECIFICATION

### DESIGN AND MANUFACTURE OF A SHIELDED FORKLIFT

Rev. 0

Classification: NSR – Non Safety related


Prepared by:  Date: 29 / 02 / 2024  
Aljaž Petančič – Radwaste Management Engineer

Reviewed by:  Date: 29 / 02 / 2024  
Jože Božič – Mechanical Maintenance Specialist

Reviewed by:  Date: 29 / 2 / 2024  
Milan Simončič – Chemistry Superintendent

Reviewed by:  Date: 29 / 02 / 2024  
Matjaž Gričar – Project Manager

Approved by:  Date: 29 / 02 / 2024  
Mario Gluhak – Technical Director

Approved by:  Date: 13 / 02 / 2024  
Božidar Krajnc – Engineering Director

## TABLE OF CONTENTS

|                                                                       |   |
|-----------------------------------------------------------------------|---|
| 1. Activity.....                                                      | 3 |
| 2. Scope .....                                                        | 3 |
| 3. Safety classification.....                                         | 3 |
| 4. Type of service .....                                              | 3 |
| 5. Codes , Standards and Procedures.....                              | 3 |
| 5.1 Familiarity with NPP K rško Documentation and Procedures .....    | 3 |
| 6. Identification of equipment and components .....                   | 3 |
| 7. Technical requirements .....                                       | 4 |
| 7.1 The shielded forklift shall meet the following requirements:..... | 4 |
| 7.2 The mast shall meet the following requirements:.....              | 4 |
| 7.3 The gripper shall meet the following requirements:.....           | 4 |
| 7.4 Driving requirements: .....                                       | 5 |
| 7.5 Safety functions .....                                            | 5 |
| 7.6 Shielding .....                                                   | 5 |
| 7.7 Documentation.....                                                | 5 |
| 8. Qualification Requirements.....                                    | 6 |
| 9. Detail Schedule.....                                               | 6 |
| 10. Supplier's Responsibilities.....                                  | 6 |
| 11. NPP Responsibilites .....                                         | 6 |
| 12. Special requirements .....                                        | 6 |
| 13. QA Requierments .....                                             | 6 |
| 14. Appendices .....                                                  | 7 |

## **1. Activity**

- Technical specification provide requirements for the procurement of design and manufacturing of an electrical shielded forklift. The product - forklift is intended for transportation of a radioactive material (particularly stored in drums) with surface dose rates up to 100 mSv/h. The shielded forklift shall be designed in accordance with the requirements listed below so that it corresponds to the planned area of use and the intended load. The forklift design can be performed in two shielding forms: a) for drums with lower surface dose rate – up to 40 mSv/h and b) for drums with higher surface dose rate – up to 100 mSv/h.

## **2. Scope**

The scope includes:

- procurement of a shielded forklift with technical characteristics as stated and required in paragraph 7.1 and 7.2,

## **3. Safety classification**

The service is clasified as Non Nuclear Safety Related activity (all other activities).

## **4. Type of service**

The procurement of a design and manufacture of shielded forklift will be carried out via public tendering with fix price.

## **5. Codes , Standards and Procedures**

The shielded forklift shall be made in compliance with applicable regulations and standards and shall meet CE requirements and other requirements from paragraphs 7 and 8.

### **5.1 Familiarity with NPP K rško Documentation and Procedures**

N/A

## **6. Identification of equipment and components**

Electric forklift for indoor and outdoor use equipped with:

- Hydraulic gripper for drum grabbing. The sketches of drums are in the appendices 1-6.

- Radiation protection shielding (steel or lead glass).
- Cameras to provide driving through a video surveillance system.

## **7. Technical requirements**

7.1 The shielded forklift shall meet the following requirements:

- Nominal load capacity,  $Q = 4500$  kg
- Load center,  $c = 500$  mm
- Solid non-marking tires
- Wheels, number front = 2, number rear = 2
- Forks:  $d = 50$  mm,  $w = 120$  mm,  $l = 1250$  mm
- Maximum overall length,  $l_1 = 4200$  mm
- Maximum length to fork face,  $l_2 = 2950$  mm
- Maximum width,  $b_1 = 1500$  mm
- Fork carriage: side shift
- Maximum ground clearance,  $m_1 = 150$  mm
- Turning radius approximately,  $W_a = 2350$  mm
- Minimum pivoting point distance,  $a/2 = 100$  mm
- Ergonomic seat installed
- Multifunctional display
- Electro-hydraulic distributor with mini fingers / mini levers
- Forward / reverse switch and horn button installed in Grammer armrest

7.2 The mast shall meet the following requirements:

- Mast type: two stage mast with free lift
- Maximum height of mast,  $h_1 = 2500$  mm
- Minimum free lift,  $h_2 = 1350$  mm
- Minimum lift,  $h_3 = 3150$  mm
- Maximum height of extended mast,  $h_4 = 4500$  mm
- Maximum height of overhead guard,  $h_6 = 2450$  mm

7.3 The gripper shall meet the following requirements:

- The hydraulic gripper / clamp for drums must have a minimum load capacity of 2600 kg. The forklift can have more than one gripper if it is more suitable for design. That means one gripper can be intended for tall and heavy drums (up to 2600 kg), one for low and light drums (up to 900 kg). The gripper(s) shall be designed to clamp the drums (appendices 1-6 ).
- The gripper must be compatible with forklift end easily removable.

7.4 Driving requirements:

- Drive motor: minimum 2 x 12 kW
- Lift motor: power rating at S3 15%: minimum 20 kW
- Battery voltage: 80V
- Battery capacity: min 900 Ah
- Type of drive: electric
- Battery charger included

7.5 Safety functions

- Travel speed with / without load limited up to 15 km/h
- Lifting speed with load up to 0,20 m/s
- Lowering speed with load up to 0,25 m/s
- Automatic control of gripper / forks height
- Minimum climbing ability with load: 10 %
- Horn
- Alarm in reverse gear
- Flash lamp
- Cameras with cabin monitor for front (3 cameras) and rear (1 camera) visibility with sufficient resolution for safe driving

7.6 Shielding

- The forklift design shall provide efficient shielding for dose reduction. Sufficient radiation protection is required for drums with contact dose rates up to 100 mSv/h in the way that the dose on operators driving seat does not exceed 1 mSv/h.

7.7 Documentation

- Instructions or manuals for use and maintenance of the forklift.
- Instructions or manuals for use and maintenance of video surveillance system.
- Recommended spare parts list for video surveillance system.
- Dose reduction calculations; dose rate reduction factor for Cs-137 (Cesium 137) should be minimum: a) Factor 39 for drums with dose rate up to 40 mSv/h, b) Factor 99 for drums with dose rate up to 100 mSv/h so the dose at operators seat does not exceed 1 mSv/h.
- Load test report (static and dynamic report).
- Certification of shielding materials.
- Declaration for clamp/gripper.
- All required attestations and certificates for the forklift.
- FAT and SAT test reports.

## **8. Qualification Requirements**

The forklift shall be CE certified and shall be equipped with all safety equipment necessary to perform work in accordance with the instructions for use, the required standards and legal bases.

## **9. Detail Schedule**

The shielded forklift is expected to be manufactured and delivered to the client until December 20th, 2024. Upon delivery, all the required documentation shall be provided and FAT (Factory Acceptance Test) and SAT (Site Acceptance Test) confirmed by NEK representatives.

## **10. Supplier's Responsibilities**

The supplier must conduct an acceptance test at the client's location, demonstrating all the required functionalities specified in this specification.

Provide a maintenance manual and serviceman contacts.

## **11. NPP Responsibilites**

NPP will provide the supplier with access to the location.

NPP responsible personnel will be available in case of ambiguity.

## **12. Special requirements**

The forklift with its gripper/clamp, together with the load shall be able to be maneueured and driven in all areas of radwaste storage building (RWS). A drawing of RWS with dimensions is in appendices 7-9. Maximum height of RWS doors and passages is 3 m, so the forklift shall be available to transport drums underneath.

## **13. QA Requierments**

N/A

## **14. Appendices**

Appendix 1 - D1 drum

Appendix 2 – D6 drum

Appendix 3 – T2 drum

Appendix 4 – T1 drum

Appendix 5 – H2 drum


Appendix 6 – H1 drum

Appendix 7 – RWSB floor plan 1

Appendix 8 – RWSB floor plan 2

Appendix 9 – RWSB floor plan 3

## ATTACHMENT 1: CONTAINER DRAWINGS




### CONTAINER D1

**Material:** CS

**Weight:** 23 kg

**Volume (net):** 208 dm<sup>3</sup>




**CONTAINER D6**

**Material: CS**

**Weight: 37 kg**

**Volume (net): 320 dm<sup>3</sup>**




**CONTAINER T2 (OVERPACK)**

**Material: CS**

**Weight: 135 kg**

**Volume (net): 864 dm<sup>3</sup>**




**CONTAINER T1 (OVERPACK)**

**Material: CS**

**Weight: 117 kg**

**Volume (net): 869 dm<sup>3</sup>**




**CONTAINER H2**

**Material: SS**

**Weight: 450 kg**

**Volume (net): 150 dm<sup>3</sup>**




**CONTAINER H1**

**Material: SS**

**Weight: 65 kg**

**Volume (net): 200 dm<sup>3</sup>**




2014年12月10日

10-03-2011  
243911


[illegible]

|                                                                                                                                                            |                                       |  |                           |
|------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------|--|---------------------------|
| PERUSAHAAN ELEKTROKIPA PRIGU<br>NUCLEAR POWER PLANT KORDO<br>MOOL PUMP LAYOUT DRAWING<br>RAS BASTE TUNGGU A/D/A PWS<br>(1:1000) 0100<br>DESIGN ENGINEERING |                                       |  |                           |
|                                                                       | DESAIN KIRI & KANAN<br>(KIRI) (KANAN) |  | AKSI, TUNGGU<br>10.000000 |
| PERUSAHAAN<br>ELEKTROKIPA                                                                                                                                  | 0.004 400 500 1000                    |  | 0.000000                  |
| MECL-RWS-02                                                                                                                                                |                                       |  |                           |





NOTES:  
1. REF. DRAWING 419-004  
2. FOR DETAILS SEE DRAWINGS 419-202 TO 419-220



Replaced Manual Drawing: NA  
Original Design Firm: BEL d.d.  
Last Revision And Date: NA

THIS IS A CAD DRAWING AND SHOULD NOT BE REVISED OR MODIFIED MANUALLY

NUKLEARNA ELEKTRARNA KRSKO  
NUCLEAR POWER PLANT KRSKO  
FINAL PLANT LAYOUT  
RAIOWASTE STORAGE FACILITY  
EL. 105.00

|                    |            |                 |           |
|--------------------|------------|-----------------|-----------|
| DESIGN ENGINEERING |            | KRSKO, SLOVENIA |           |
| 1. MADE            | 2. CHECKED | 3. JACORN       | 4. JACORN |
| 1. EC              | 2.         | 3.              | 4.        |
| 1. EC              | 2.         | 3.              | 4.        |
| C-004-405          |            | 2               |           |
| DRAWING NUMBER     |            | REV             |           |